ENGINEERING DEPARTMENT

BANGALORE DIVISION.

Notification dated 27th September 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 24th October 1939, for constructing a building for the machine house at Hessarghatta Grass Farm.

2. Tenders in the prescribed form obtainable on payment of Re. 0-4-0 per form from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for constructing machine house at Hessarghatta, Grass Farm." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan (enclosed in the sealed cover) for having credited into the treasury the deposit amount of Rs. 150 under 17 (*a*) P. W. Deposits or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 25th October 1939 at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore, on all working days, between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 3 each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page, noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of January 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Re. 1 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer, shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, sump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities for constructing a Machine House in Hessarghatta Grass Farm.

Sl. No.	Items of work	Per	Rate	Quantity	Rate to be quoted in	
					Words	Figures
			Rs. a. p.		Rs.	Rs.
1	Earthwork excavating for foundation ..	C.yd.	0 3 0	46		
2	Burnt stone jelly concrete in lime mortar ..	C.ft.	0 3 6	441		
3	Size stone in mud faces hammer dressed with bond stones 6′ apart in each layer	,,	0 3 6	763		
4	Burnt brick in clay for superstructure ..	,,	0 3 0	2,242		
5	Burnt brick in mortar for sides of doors and windows ½..	,,	0 4 0	103		
6	Burnt stone slabs 6″ thick roughly dressed and fixed in mortar	S.ft.	0 3 0	93		
7	Do 4″ thick do ..	,,	0 4 0	175		
8	Teak wood doors 5′×7′ and 4′×7′ with frames 5″×4″ and 4½″×3½″ with shutter 1½″ thick with iron clamps and fittings, etc., complete	,,	1 4 0	63		
9	Teak wood windows frames 1′×5′ and 4′×1¾′ with 4″×1½″ and 3″×3¾″ shutters iron bars, etc., complete	,,	1 8 0	130		
10	Roofing with cement asbestos sheeting on angle iron purlins fixed on trusses ..	Sqr.	36 0 0	31.6		
11	Cement Asbestos ridging	R.ft.	1 4 0	87½		
12	Plastering with chunam plaster	Sqr.	3 0 0	39.87		
13	Colour washing	,,	0 5 0	15.6		
14	White washing	,,	0 3 9	24·3		
15	Flooring with 3″ stone jelly concrete in lime mortar over which 1½″ cement concrete and plastered with cement rough ..	,,	20 0 0	4.60		
16	Flooring with gravel 6″ thick and the top washed with 2 coats of cowdung ..	,,	1 8 0	16.60		
17	Approved green painting 2 coats ..	,,	3 8 0	20.60		
18	Cement pointing to basement with colour washing	,,	3 0 0	1.20		
19	Granite jelly concrete (one inch size) in cement mortar (1 : 2 : 4) laid in 4″ layer and well consolidated	C.ft.	0 12 0	36		

Notification dated 28th September 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 25th October 1939, for constructing an additional block to the Middle School Building at Dodballapur.

2. Tenders in the prescribed form obtainable on payment of four annas per form, from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for constructing an additional block to the Middle School Building at Dodballapur." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender enclosed in the sealed cover must be accompanied by a duplicate challan for having credited into the treasury the deposit amount of Rs. 265 under 17(*a*) P. W. Deposits, or Mysore Government Bonds duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 26th October 1939 at Bangalore. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 3 for each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of February 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 2 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should

bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities for constructing an additional Block to the Government Middle School at Dodballapur.

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Words	Figures
			Rs. a. p.		Rs.	Rs.
1	Earthwork excavation for foundation and filling in basement including watering and tamping, etc., complete ..	C.yd.	0 3 0	94		
2	Burnt stone jelly concrete in lime mortar 1 : 2 : 4	C.ft.	0 3 6	623		
3	Burnt stone size in clay with through stones at every 6 feet apart in each layer ..	,,	0 3 6	2,522		
4	Burnt brick in clay with bond stones, etc. ..	,,	0 3 0	2,929		
5	Burnt brick in mortar	,,	0 3 6	779		
6	Reinforced cement concrete roofing 6" thick with ½" bars at 5" C to C and ½" rods at 12" C to C including 2" surki concrete at top 2 courses of flat tiles, top and bottom plastered, etc., complete ..	Sqr.	70 0 0	18.66		
7	Burnt stone slabs 6" thick one line dressed and fixed in lime mortar	S.ft.	0 5 0	952		
8	Providing and fixing teakwood door frame 4"×3" in section with pannelled shutters 1½" thick including all iron fittings, etc., complete	S.ft	1 8 0	137		
9	Providing and fixing teakwood windows frame 5"×3" in section with pannelled shutters 1" thick iron bars of ¾" dia. and all iron fittings, etc., complete ..	,,	1 12 0	240		

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Words	Figures
			Rs. a. p.		Rs.	Rs.
10	Providing R. C. ventilators as per approved design	S.ft.	0 12 0	108		
11	Block cornice in burnt brick in mortar as per design with plastering, etc., complete ..	R.ft.	0 4 0	265		
12	Chunam plastering	Sqr.	2 8 0	62·19		
13	Chunam pointing to basement	,,	1 8 0	23·94		
14	Parapet wall 2′×$\frac{3}{4}$′ with burnt brick in mortar with pillasters and plastering, etc., complete as per plan	R.ft.	0 12 0	147		
15	Parapet wall 1$\frac{1}{2}$′×$\frac{3}{4}$′ with burnt brick in mortar with pillasters white-washing, etc., complete as per plan	,,	0 10 0	82		
16	Providing and fixing R. S. girders including hoisting and fixing and boxing, etc., complete	Cwt.	15 0 0	36·32		
17	Flooring with 1$\frac{1}{2}$″ cement concrete on 3″ burnt stone jelly concrete and plastered with cement $\frac{1}{2}$″ thick mixed with red ochre and cut into squares and smoothened	Sqr.	20 0 0	14·20		
18	Providing zinc sheet spouts 3″ dia. for the main building	No.	0 8 0	8		
19	Do do for verandah ..	,,	0 8 0	4		
20	Providing R. C. fret work in the parapet wall including fixing as per approved design	S.ft.	1 0 0	72		
21	White washing, 2 coats	Sqr.	0 3 9	40·00		
22	Colour washing do	,,	0 5 0	20·00		
23	Lac Factory green paint to doors and windows, two coats	,,	3 8 0	10·00		

Notification dated 30th September 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 26th October 1939, for additions and alterations to the Urdu Boys' Middle School building at Closepet.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for additions and alterations to the Urdu Boys' Middle School Building at Closepet." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender enclosed in the sealedc over must be accompanied by a duplicate challan for having credited into the treasury the deposit amount of Rs. 125 under 17(*a*) P. W. Deposits or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 27th October 1939, at Bangalore Division. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore, on all working days between 11 A.M. and 5 P.M. and may be obtained from that Officer on payment of Rs. 3 each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page, noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of January 1940, failing which, the Executive Engineer may, at his discretion, levy a penalty of Rs. 0-13-0 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills, and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary, provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities required for the additions and alterations to the Urdu Boys' Middle School Building at Closepet.

No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
	Alterations.			Rs. a. p.	Rs.	Rs.
1	Removing doors at A and B by dismantling masonry and fixing them at A and B with necessary masonry marked on the plan	Each	4	1 8 0		
2	Removing windows at C, D, E and F and refixing them in front side at C, D, E and F, as marked on the plan with necessary masonry	,,	4	1 0 0		
3	Dismantling old masonry	C.ft.	154	0 0 4		
4	Burnt brick in mortar for closing gaps, etc.	,,	206	0 3 9		
5	Plastering with lime mortar	Sqr.	3·00	2 12 0		
6	Removing old Mangalore tiled roof with reepers and rafters and stacking them.		6·48	1 0 0		
7	Removing burnt stone pillars and fixing them in new position	Each	10	1 0 0		
8	Dismantling the retaining wall of Verandah	C.ft.	107	0 0 4		
9	Burnt stone slabs 6" thick, one line dressed and fixed	S.ft.	47	0 5 0		
10	Removing and refixing R. C. sunshades ..	Each	2	1 0 0		
11	Providing and fixing R. C. sunshades ..	,,	2	7 0 0		
	Additions.					
1	Earthwork excavation of foundation and filling in basement	C.yd.	55	0 3 0		
2	Burnt stone jelly concrete in lime mortar	C.ft.	480	0 3 6		
3	Burnt size stone in lime mortar faces hammer dressed with bond stones at every six feet in each layer	,,	881	0 4 0		
4	Fixing old burnt stone slabs in mortar ..	S.ft.	54	0 1 0		
5	Burnt brick in mortar	C.ft.	1,622	0 3 9		
6	Teakwood wrought and put including two coats of wood oiling	,,	108	4 8 0		
7	Roofing with 1st Class Mangalore pattern Yelahanka tiles on 2"×1" teak batten wood oiled including the fixing of eave tiles by a teak batten	Sqr.	11·56	22 0 0		
8	Roofing with Mangalore tiles old with old rafters and reepers, etc. ..	,,	5·61	3 0 0		
9	Providing and fixing galvanized iron sheets 22 guage with teakwood plank ¾" thick 1½' wide on each side for valley with cement plastering, etc. ..	R.ft.	25	2 0 0		
10	Fixing new Mangalore tiles with reepers, etc.	Sqr.	0·62	22 0 0		

No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
				Rs. a. p.	Rs.	Rs.
11	Providing and fixing teakwood doors 4′ ×7′ with frames 4½″×3½″ in section with pannelled shutters 1½″ thick having top 1½ fixed with expanded metal with iron clamps and fitting including two coats of silicate painting .. .	S.ft.	56	1 8 0		
12	Providing and fixing teakwood windows 3′ ×5′ with frames 3½″×4″ in section ¾″ dia. iron bars and pannelled shutters 1¼″ thick iron clamps iron fittings, etc., including two coats of silicate painting	,,	60	1 10 0		
13	Providing teakwood windows with ¾″ iron bars without shutters having expanded metal fixed as per existing design including two coats of silicate painting.	,,	58	1 4 0		
14	Stucco plastering with lime mortar with mortar bands alround as per design including cement wash	Sqr.	3·60	4 8 0		
15	Flooring with burnt stone slabs 3″ to 4″ thick one line dressed over 3″ burnt stone jelly concrete and pointed with cement	,,	6·60	30 0 0		
16	Plastering with lime mortar	,,	29·12	2 12 0		
17	Removing and refixing Cuddapah slabs on new 3″ thick burnt stone jelly concrete.	,,	1·44	8 0 0		
18	Cement pointing	,,	4·00	3 0 0		
19	Removing and refixing the steps in mortar with necessary masonry	S.ft.	96	0 1 0		
20	Mortar band over roof	R.ft.	48	0 2 0		
21	Providing burnt stone slabs 6″ thick and fixing in mortar	S.ft.	74	0 4 6		

N. LAKSHMINARASIMIAH,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification dated 20th September 1939.

The attention of the public is invited to the detailed notification, dated 19th September 1939, published on pages 1954-1956, Part VI of the *Mysore Gazette*, dated 28th September 1939, regarding tenders for the maintenance work to Nambihalli Doddakere, Register No. 93-426 of Srinivaspur Taluk.

The last date for receiving tenders is 16th October 1939 up to 2 P.M.

Abstract Notification dated 20th September 1939.

The attention of the public is invited to the detailed notification, dated 19th September 1939, published on pages 1956-1959, Part VI of the *Mysore Gazette*, dated 28th September 1939, regarding tenders for the construction of Quarters for the Inspector of Mines and Explosives at Kolar Gold Fields.

The last date for receiving tenders is 16th October 1939 up to 2 P.M.